



ZuildUp

CUSTOM HOME QUOTATION

Don't just build, Zuild!

Mr. QC Baseline 2026-05-21

QC Plot 27x57
Sector QC
Gurgaon

21 MAY 2026

24+ YEARS EXCELLENCE

450+ QUALITY CHECKS

TRANSPARENT PRICING

ON-TIME DELIVERY

QUOTE ID

ZUI-2026-1022

Quote valid until 20 Jul 2026

WHY ZUILDUP

Tech-Enabled Construction. Quality Assured.

Transparent pricing, assured quality, and on-time homes — delivered with 24+ years of excellence and 450+ quality checks per build.

Our Vision

To make home construction simple, transparent, and reliable for every land owner.

Our Mission

To combine engineering excellence, top-grade materials, and customer-first service for the best construction experience.
24+ YEARS OF EXPERIENCE

OUR PROCESS

01 Consultation & Planning

We understand your vision, requirements, and budget. Free site visit and feasibility analysis included.

02 Design & Approvals

Our architects prepare detailed plans and 3D views. Multiple optimized design options provided.

03 Foundation & Structure

Construction begins with strong foundations and structural work using premium-grade materials.

04 Construction & Finishing

MEP, interiors, flooring, painting, and fixtures completed as per approved specifications.

05 Final Handover

Quality inspection, final walkthrough, documentation, and smooth handover of your home.

WHY FAMILIES CHOOSE US

24+ Years Excellence

Award-winning architectural design and construction expertise.

450+ Quality Checks

Comprehensive quality assurance at every stage ensuring exceptional standards.

On-Time Delivery

98% of projects completed on schedule. We value your time and commitments.

Transparent Pricing

No hidden costs. Complete cost breakdown provided upfront with detailed quotations.

Expert Team

50+ skilled professionals including licensed architects and certified contractors.

Live Tracking

Real-time construction updates enabling clients to monitor progress anytime.

WARRANTY PROMISE

Structure Warranty**Up to 15 Years**

Coverage on structural integrity

Window Profiles**Up to 10 Years**

Warranty on window frames & profiles

Interiors & Finish**Up to 5 Years**

Wardrobe, Modular Kitchen, Vanity & similar items

Internal Doors**Up to 5 Years**

Coverage on all internal door units

Seepage Protection**Up to 1 Year**

Extended warranty for seepage, electrical wiring & cracks in paint / plaster can be obtained at an additional cost of ₹15 / Sq.ft / Annum

Anti-Termite**Up to 1 Year**

Treatment coverage against termites

Electrical Wiring**Up to 1 Year**

On all electrical wiring used by ZuildUp

General & AMC**Up to 1 Year**

Everything else done by ZuildUp + AMC

3rd Party Products**Up to Manufacturer**

As provided by the original manufacturer

STEP 1

Area Calculation

Built-up area derived from plot dimensions, coverage and the chosen build configuration. Each zone bills at a different rate (see Cost Calculation).

Plot: 170 sq.yd / 1,530.00 sq.ft**Dims:** 27ft × 57ft**Build:** Stilt + 3 Floors**Lift:** Yes

Floor Area Summary

FLOOR	LIFT & STAIRCASE	COVERED AREA	SEMI COVERED	OPEN AREA
Stilt	150.00 sq.ft	—	997.50 sq.ft	544.50 sq.ft
Ground Floor	150.00 sq.ft	997.50 sq.ft	135.00 sq.ft	—
First Floor	150.00 sq.ft	997.50 sq.ft	135.00 sq.ft	—
Second Floor	150.00 sq.ft	997.50 sq.ft	135.00 sq.ft	—
Terrace (Mumty)	150.00 sq.ft	—	—	1,132.50 sq.ft
Total	750.00 sq.ft	2,992.50 sq.ft	1,402.50 sq.ft	1,677.00 sq.ft

Area	Description	Est. Size
A	Zone A — ₹2,300/sqft	
Ground Floor	Floor Area (1,147.50) – Lift (25) – Staircase (125)	997.50
First Floor	Floor Area (1,147.50) – Lift (25) – Staircase (125)	997.50
Second Floor	Floor Area (1,147.50) – Lift (25) – Staircase (125)	997.50
Lift	5 levels × 25 sq.ft	125.00
Total Zone A		3,117.50

Area Calculation (continued)

Area	Description	Est. Size
B Zone B — ₹1,200/sqft		
Stilt	Floor Area (1,147.50) – Lift (25) – Staircase (125)	997.50
Balcony	27ft × 5ft × 3 floors	405.00
Staircase	5 levels × 125 sq.ft	625.00
Total Zone B		2,027.50
C Zone C — ₹600/sqft		
Terrace	Floor (1,147.50) + 1 balcony (135.00) – Staircase (125) – Lift (25)	1,132.50
Ramp	27ft × 6ft	162.00
Setback	Plot Area (1,530.00) – Floor Area (1,147.50)	382.50
Total Zone C		1,677.00
D Zone D — ₹15/L		
Underground Water Tank	3 floors × 2,000 L	6,000 L
Total Zone D		6,000 L
Total Built-up Area (excluding water tank capacity)		6,822.00 sq.ft

STEP 2

Cost Calculation

Each zone's area multiplied by its applicable rate. Lift cost added separately if enabled. Taxes and any liaisoning are quoted separately, outside this document.

Zone	Area	Rate	Total
A Zone A	3,117.50	₹2,300/sqft	₹71,70,250
B Zone B	2,027.50	₹1,200/sqft	₹24,33,000
C Zone C	1,677.00	₹600/sqft	₹10,06,200
D Zone D	6,000 L	₹15/L	₹90,000
Sub-total (zones)			₹1,06,99,450
Lift Machine			₹10,00,000
Construction Total			₹1,16,99,450

Final billed at actual brand and finish selection. GST and any liaisoning fees are quoted separately outside this document.

STEP 3

Detailed Specifications

Every line item, every brand, every rate. Brand options shown are indicative; final selection confirmed at the brand-picker stage.

Design & Drawings 1 ITEMS

ITEM	RATE	DESCRIPTION
Architectural Layout	—	2D Architectural DesignModern 3D Elevation Structural Design MEP Drawings All construction work to be carried out as per approved plan No. of 2D floor plan iteration is not a constrain. The number of changes will be done till the floor plan is finalized.

Structure 15 ITEMS

ITEM	RATE	DESCRIPTION
Steel	—	Rathi Fe500/ Fe550 4.5Kg per sqft Any variation above and below 4.5kg is charged and refunded on pro rata basis.
Cement	—	Shree/Dalmia/Ambuja Same brand shall be used for all RCC, brickwork, and plastering works.
Bricks	—	Baghpat (U.P) A Class Red Brick External walls shall be constructed using 9-inch (4.5 inch in case of common wall) thick brickwork and internal partition walls shall be 4.5-inch thick
Concrete	—	M25 RCC work in Slab, Beam, Column, and Foundation to be carried out. M25 ratio is 1:1:2 (Cement : Sand : Coarse Aggregates). Proper use of Vibrators and Cover Blocks in Slabs, beams, columns and foundation.
Plinth, Floor and Stilt Level	—	Plinth is considered at 2 ft height. Floor to Ceiling Height (Clear Height) is 10 ft on first and second floors. Stilt height as per the government norms
Aggregates (Rodi)	—	20mm & 10mm Most superior bluish color aggregates to be used in all concrete work. PCC in Foundation / Stilt and
PCC in Foundation / Stilt and Terrace	—	Plinth is considered at 2 ft height. Floor to Ceiling Height (Clear Height) is 10 ft on first and second floors. Stilt height as per the government norms
Plaster Work	—	Interior Plaster : 8-10mm thick with ratio of 1:2:3 (Cement:Coarse Sand:Fine Sand). Single coat plaster of 8-10mm thick would be provided. Exterior Plaster : 12-15mm thick with ratio of 1:2:2 (Cement:Coarse sand:Fine Sand). Double coat plaster totaling to 12-15 mm would be provided for durability and strength
Compound Wall	—	4.5 Inch thick compound wall will be provided with 6 ft height from the plinth level on open areas perimeter
Parapet Wall	—	9 inch thick wall with 3.3 ft will be provided on terrace on entire terrace perimeter.
Curing	—	Sika Antisol All RCC and masonry works shall be properly cured using continuous water curing methods to maintain adequate moisture for hydration of cement. Minimum 12-14 days for RCC work, minimum 10-14 days for brickwork and plaster twice a day
Waterproofing	—	Sika/Dr. Fixit LW+ (pidilite) Concrete used anywhere is infused with waterproofing crystalline compound Waterproofing coat is done in wet areas like balcony, bathrooms, underground sump Gola is created on terrace on joint of slab and parapet wall. Waterproofing compound is added to external plaster.

Structure 15 ITEMS

ITEM	RATE	DESCRIPTION
Anti-Termite Treatment	—	Bayer / Terminator (pidilite) Double Layer Protection System (DLPS) FIRST STEP : Termite soil treatment begins preconstruction for complete building. To be done at plinth level with Bayer & Terminator (Pidilite) antitermite chemical. SECOND STEP : Systematic piping network for uniform distribution across the area. Designed for efficiency, durability, and leak-proof performance. TEAM AT ZUILD USES DLPS, SO AS TO ENSURE MAXIMUM PROTECTION TOWARDS TERMITE.
Misc	—	Provision for water purifier, dishwasher, and other kitchen appliances shall be provided, including necessary inlet and outlet plumbing points. A bib cock shall be provided for the washing machine in the utility area or at a location as per the architectural drawings.
Assumptions	—	Site level should not be less than 1 ft below the road level. Foundation is considered combination of isolated and combined footing 5 ft-6ft below the natural ground level

Bathroom & Toilet 7 ITEMS

ITEM	RATE	DESCRIPTION
Sanitary Ware and CP Fitting	₹25,000 per Bathroom	Hindware Italian Collection Premium quality sanitary ware including wall-mounted EWC, wash basin, shower head, and diverter from Hindware (Italian Collection) will be provided upto the specified value.
Bathroom Accessories	₹3,000 per bathroom	Premium accessories including mirror, towel rod/ring, soap dish, etc., up to the specified value.
Bathroom Geyser	₹5,000 per bathroom	Crompton/Bajaj One geyser per bathroom from reputed brands like Crompton / Bajaj, within the defined budget.
Exhaust Fan	₹1,250 per kitchen	Havells Provision and installation of a wall-mounted exhaust fan for proper ventilation.
Bathroom Flooring	₹50 per sq ft	Anti-skid floor tiles (sizes: 1'×1' or 2'×2') to ensure safety and durability.
Bathroom Wall Cladding	₹50 per sq ft	Wall tiling up to ceiling height (sizes: 1'×1.5' or 2'×2') providing a clean and moisture-resistant finish.
CPVC Fittings	—	Astral Complete plumbing system using high-quality CPVC pipes and fittings from trusted brands to ensure longevity and leak-proof performance.

Kitchen 8 ITEMS

ITEM	RATE	DESCRIPTION
Kitchen Counter Granite	₹120 per sq ft	Polished granite (16–18 mm thick) shall be provided for the kitchen counter with double-layered nosing, mounted on a 4-inch RCC slab.
Sink and Faucet	₹8,000 per kitchen	Double-bowl stainless steel sink with faucet shall be provided, ISI Brand SS304 Grade double bowl sink to be provided.
Kitchen Geyser	₹2,500 per kitchen	Crompton/Bajaj One geyser per bathroom from reputed ISI mark brands like Crompton / Bajaj, within the defined budget.
Exhaust Fan	₹1,250 per kitchen	Havells Provision and installation of a wall-mounted exhaust fan for proper ventilation.
CPVC Fittings	—	Astral Complete plumbing system using high-quality CPVC pipes and fittings from trusted brands to ensure longevity and leak-proof performance.
Modular Kitchen	₹1,00,000 per kitchen	Modular kitchen made of Plyboard with laminates, including soft close channels from Ozone/Godrej, with well-designed drawers and corner solutions.
Hob and Chimney	₹20,000 per kitchen	Faber/Kaff Built-in hob and chimney from Faber / KAFF shall be provided within the specified budget range.
Misc	—	Provision for water purifier, dishwasher, and other kitchen appliances shall be provided, including necessary inlet and outlet plumbing points. A bib cock shall be provided for the washing machine in the utility area or at a location as per the architectural drawings.

Doors, Windows & Wardrobe 10 ITEMS

ITEM	RATE	DESCRIPTION
Main Entry Door	₹20,000 per door	32 mm thick premium flush door shutter with polished/laminated finish, fixed on a seasoned hardwood frame (marandi/sal wood), complete with SS 304 hinges, SS tower bolts, door stopper, handle, and all necessary fittings and hardware.
Main Door Lock	₹3,000 per door	Godrej / Yale Premium quality digital door locks from Godrej Yale make shall be provided, suitable for the main door ensuring durability, safety, and smooth operation.
Internal and Bathroom Doors	₹12,000 per door	Flush door shutters with laminate/paint finish, installed on hardwood frames, complete with SS 304 hinges, SS tower bolts (where applicable), door stopper, handle, and all required fittings and hardware. Internal and Bathroom Door
Internal and Bathroom Door Lock	₹12,000 per door	Flush door shutters with laminate/paint finish, installed on hardwood frames, complete with SS 304 hinges, SS tower bolts (where applicable), door stopper, handle, and all required fittings and hardware. Internal and Bathroom Door
Terrace and Stilt/Staircase Entry Door	—	Plinth is considered at 2 ft height. Floor to Ceiling Height (Clear Height) is 10 ft on first and second floors. Stilt height as per the government norms
Sliding Door/ Windows	₹600 per sq ft	Prominence · EITI UPVC sliding doors/windows with 3-track system (2 glass panels and 1 mosquito mesh track) from Prominence / EITI or equivalent make, complete with all necessary fittings and hardware.
Door Hinges & Stopper	—	4 Stainless Steel 304 hinges for each door
Door Height	—	7'6" to 8' as per approved plan
Tower Bolt	—	18-24 inch, Stainless Steel Finish
Modular/ WalkIn Wardrobe	₹800 per sqft	Laminated finished wardrobe / walk-in wardrobe constructed using Ply board for carcass and shutters. All panels shall be edge-banded with PVC edge band for durability and moisture resistance. External finish shall be in laminate finish only. Internal surfaces shall be finished in laminate / pre-laminated boards. Hardware shall include soft-close hinges and telescopic drawer channels from reputed brands such as Godrej/Ozone or equivalent. Handles shall be standard SS / aluminium. The wardrobe shall include basic internal layout comprising shelves, hanging rods, and 2 drawer units, designed for functional storage. Lofts, fluted glass, acrylic/PU finish, premium accessories, and specialized fittings shall not be part of this scope.

Flooring 6 ITEMS

ITEM	RATE	DESCRIPTION
Floor Flooring	₹50 per sq ft	Vitrified tiles in living, dining, kitchen and all bedrooms, with polishing
Balcony Flooring	₹50 per sq ft	Anti-skid tiles (2'×2') for balconies, with cementitious grouting.
Staircase Flooring	₹70 per sq ft	18mm Granite shall be provided on treads and risers, with proper edge nosing and chamfering Height of the raiser would be confirmable, will be planned at the floor plan stage.
Terrace Flooring	₹40 per sq ft	Anti-skid cool roof top tiles (2'×2') for terrace, with cementitious grouting.
Stilt Flooring	₹70 per sq ft	18mm Granite on treads and risers, with proper nosing and chamfering
Skirting	—	100 mm (4") high skirting shall be provided along all wall edges in respective areas, matching the flooring material (vitrified tiles / granite). Skirting shall also be provided along staircase walls using matching granite, with proper edge finishing

Electrical Work 12 ITEMS

ITEM	RATE	DESCRIPTION
Electrical Wire	—	FR grade Finolex/Polycab/Havells Wires FR grade copper wiring shall be provided with appropriate sizing for light, power, and AC circuits to ensure safe load handling.
Electrical Wire Specification	—	10 sq. mm for main panels, 4 sq. mm for power and AC circuits, and 1.5 sq. mm for lighting circuits, ensuring safe load distribution without overloading.
Conduit Pipes & Boxes	—	Astral · AKG ISI marked PVC conduits shall be provided, with heavy-duty conduits in slabs and medium-duty conduits in walls, with separate routing for light and power circuits.
Switch & Sockets	—	Anchor/Havells Modular switches and sockets in white finish from Anchor/Havells equivalent make shall be provided. No. of switches and sockets will not be a constrain Ceiling Fans (Second and Third
Split AC Provision	—	One provision each in all bedrooms, drawing room, and living/kitchen area. Copper piping (average up to 10 m per AC) along with necessary electrical wiring shall be provided. Outdoor units shall be placed on the respective floor.
Downlighters	—	Philips · Osram Downlighters from Philips / Osram or equivalent make shall be provided.
Cove Strip Lights	—	Philips · Osram LED strip lights from Philips / Osram or equivalent make shall be provided in cove areas
UPS Wiring	—	Provision for UPS wiring shall be provided for each floor.
EV Charging Point	—	Provision for one electric vehicle charging point shall be provided per floor.
Solar Electrical Provision	—	Provision for solar electrical system shall be included.
MCB/ELCB	—	Havells MCB and ELCB protection shall be provided for each floor.
Earthing	—	Earthing shall be done using copper strip / Chemical earthing for effective grounding and safety.

Water Management 5 ITEMS

ITEM	RATE	DESCRIPTION
Underground Water Tank	2000 liters per floor	2000 liters per floor Brickwork underground sump shall be constructed for each floor as a separate unit, finished internally with commercial tiles. Waterproofing shall be carried out using approved systems from Dr. Fixit / Sika or equivalent. Overhead Water Tank 1000 liters per floor 1000 liters per floor Triple-layer overhead water tanks of 1,000 litres capacity shall be provided for each floor, Tanks shall be from Astral or equivalent make.
Overhead Water Tank	2000 liters per floor	2000 liters per floor Brickwork underground sump shall be constructed for each floor as a separate unit, finished internally with commercial tiles. Waterproofing shall be carried out using approved systems from Dr. Fixit / Sika or equivalent. Overhead Water Tank 1000 liters per floor 1000 liters per floor Triple-layer overhead water tanks of 1,000 litres capacity shall be provided for each floor, Tanks shall be from Astral or equivalent make.
Water Motor	—	2 Crompton Greaves motor for each floor 1 HP water pump shall be provided for each floor, connecting individual underground sump to corresponding overhead tank. Pumps shall be from Crompton Greaves or equivalent make.
Rainwater Harvesting	—	Rainwater harvesting pit shall be constructed as per applicable government norms
Discharge PVC Pipe	—	All necessary PVC discharge pipes and connections shall be provided for proper water flow, drainage, and system integration. High-grade PVC pipes of 4-inch or 6-inch diameter, as per site conditions and design requirements, shall be used. Ceiling & Elevation

Ceiling & Elevation 2 ITEMS

ITEM	RATE	DESCRIPTION
False Ceiling	—	POP cove false ceiling shall be provided in living, dining, and all bedrooms using Sakarni POP or equivalent make, including base level ceiling. Any additional design elements or premium features shall be as per design.
Elevation	—	Front side no HPL panels, basic esthetical look is taken. Back side of the building shall be finished with chapai dana and roller finish. Safety & Security

Safety & Security 1 ITEMS

ITEM	RATE	DESCRIPTION
CCTV Camera	₹40,000 lumpsum	CCTV camera system with cameras worth ₹40,000 and basic wiring as per layout.

Paint & Polish 4 ITEMS

ITEM	RATE	DESCRIPTION
Internal Wall Paint	—	Asian Paints (Tractor Shyne Emulsion) 2 coats will be provided over 1 layer of primer and 2 layer of putty
Exterior Wall Paint	—	Berger (Weathercoat Glow) Weathercoat glow Berger will be provided on the exterior side.
Putty	—	JK Birla Putty 2 coats of putty to be provided
Polish	—	Melamine Polish in Matte/Glossy Finish as per owner's choice General Aspects

General Aspects 6 ITEMS

ITEM	RATE	DESCRIPTION
Main Gate	—	Bifold MS Main Gate at front as per design
Staircase & Balcony Railing	—	Staircase Railing - MS Steel designer railing Balcony Railing as per design MS CNC cut
Vibrators	—	Used to consolidate layers in footings, columns, beams & roof slabs
Brickwork Mortar	—	9" brickwork not leaner than 1:6; 4½" brickwork not leaner than 1:4
Soil Test	—	Soil Test to be done before construction. Costing is included.
Lift Machine	₹10,00.000 taken as wallet	Includes all civil, electrical, paint, polish, exhaust, and earthing work. Entry on all floors. SPECIFICATIONS